Regional Municipality of Durham

Bid Opportunity: T-1034-2026 - General Contractor for the construction of 409 Centre Street South in Whitby

Closing Date: Friday, November 06, 2026 2:00 PM

Addendum number 5 – October 27, 2026

This addendum will form a part of the bid documents for the above-noted bid and shall be read in conjunction therewith. This addendum will take precedence over all requirements of the original bid documents and any addenda issued previously.

Bidders shall acknowledge receipt of this addendum with their electronic bid submission on the declaration page in the bidding system.

Attachments

1. Section 01 13 00 Delegated Design Requirements R1
2. Section 01 78 37 Extended Warranties R1
3. Section 03 51 13A Cementitious Topping
4. Section 04 20 00 Unit Masonry R1
5. Section 04 42 00A Exterior Stone Cladding
6. Section 05 50 00 Miscellaneous and Metal Fabrications R1
7. Section 06 26 00 Mass Timber Soffits, Ceiling & Wall Paneling R1
8. Section 08 80 00 Glazing R1
9. Section 09 91 00 Painting R1
10. Section 12 21 23 Window Coverings R2
11. Section 31 22 16 Growing Medium and Fine Grading R1

12. Section 32 00 00A Roadworks Detailed Specifications R1
13. Section 32 12 33 Coloured Asphalt Surface Coating
14. LG Commercial Washer & Dryer Cut Sheets
15. Furniture Specifications R1
16. Cosine Report
17. Topographic Survey_Ref. No. 23-431-06
18. MD15_409 Centre IFT_Construction Management Report_V2
19. MD19_409 Centre IFT_Construction Vibration Zone of Influence Report_V2
20. A0201 - Construction Assemblies – Exterior
21. A1401 - Floor Plan - Level 1
22. A1403 - Floor Plan - Level 3
23. A1500 - Reflected Ceiling Plan – Basement
24. A1501 - Reflected Ceiling Plan - Level 1
25. A1700 - FF&E Plan - Level 1 Amenity Space
26. A2230 - Site-Building Elevations
27. A2231 - Site-Building Elevations
28. A6110 - Schedule - Room Finish
29. A6120 - Schedule – Door
30. A6130 - Schedule - Interior Glazed Screen
31. A6250 - Exterior Glazing & Window Schedule
32. A8201 - Casework – Elevations
33. A8301 - Millwork - Elevations, Sections & Section Details
34. CM-1 – Construction Management Plan
35. L.1 – Landscape Plan
36. L.4 – Landscape Details

Appendix D-1 Deliverables

Architectural Specifications

1. Section 00 13 00 Delegated Design Requirements R1; Replace and forms part of this Addendum.
    - Additions: Indicated in **bold** text.
    - Omissions: Indicated by ~~strikethrough.~~
2. Section 01 78 37 Extended Warranties R1; Replace and forms part of this Addendum.
    - Additions: Indicated in bold text.
    - Omissions: Indicated by strikethrough.
3. Section 03 51 13A Cementitious Topping; Add, forms part of this Addendum.
4. Section 04 20 00 Unit Masonry R1; Replace and forms part of this Addendum.
    - Additions: Indicated in **bold** text.
    - Omissions: Indicated by ~~strikethrough.~~
5. Section 04 42 00A Exterior Stone Cladding; Add, forms part of this Addendum.
6. Section 05 50 00 Miscellaneous and Metal Fabrications R1; Replace and forms part of this Addendum.
    - Additions: Indicated in **bold** text.
    - Omissions: Indicated by ~~strikethrough.~~
7. Section 06 26 00 Mass Timber Soffits, Ceiling & Wall Paneling R1; Replace and forms part of this Addendum.
    - Additions: Indicated in **bold** text.
    - Omissions: Indicated by ~~strikethrough.~~
8. Section 08 80 00 Glazing R1; Replace and forms part of this Addendum.
    - Additions: Indicated in **bold** text.

- Omissions: Indicated by ~~strikethrough.~~

9. Section 09 91 00 Painting R1; Replace and forms part of this Addendum.
   - Additions: Indicated in **bold** text.
   - Omissions: Indicated by ~~strikethrough.~~
10. Section 12 21 23 Window Coverings R2; Replace and forms part of this Addendum.
   - Additions: Indicated in **bold** text.
   - Omissions: Indicated by ~~strikethrough.~~
11. Section 31 22 16 Growing Medium and Fine Grading R1; Replace and forms part of this Addendum.
   - Additions: Indicated in **bold** text.
   - Omissions: Indicated by ~~strikethrough.~~
12. Section 32 00 00A Roadworks Detailed Specifications R1; Replace and forms part of this Addendum.
   - Additions: Indicated in **bold** text.
   - Omissions: Indicated by ~~strikethrough.~~
13. Section 32 12 33 Coloured Asphalt Surface Coating; Add, forms part of this Addendum.
14. Appendix 09: Construction Management Report R1; Replace and forms part of this Addendum.
   - Additions: Indicated in **bold** text.
   - Omissions: Indicated by ~~strikethrough.~~
15. Appendix 12: Furniture Specifications R1; Replace and forms part of this Addendum.
   - Additions: Indicated in **bold** text.
   - Omissions: Indicated by ~~strikethrough.~~
16. Appendix 14: Cosine Report; Add, forms part of this Addendum
17. Appendix 15: Topographic Survey; Add, forms part of this Addendum
18. Appendix 16: Construction Vibration ZOI Report; Add, forms part of this Addendum

Appendix D-2 Material Disclosures

Drawings - Architectural

1. A0201 - Construction Assemblies – Exterior
2. A1401 - Floor Plan - Level 1
3. A1403 - Floor Plan - Level 3
4. A1500 - Reflected Ceiling Plan – Basement
5. A1501 - Reflected Ceiling Plan - Level 1
6. A1700 - FF&E Plan - Level 1 Amenity Space
7. A2230 - Site-Building Elevations
8. A2231 - Site-Building Elevations
9. A6110 - Schedule - Room Finish
10. A6120 - Schedule – Door
11. A6130 - Schedule - Interior Glazed Screen
12. A6250 - Exterior Glazing & Window Schedule
13. A8201 - Casework – Elevations
14. A8301 - Millwork - Elevations, Sections & Section Details

Drawings – Civil

1. CM-1 – Construction Management Plan
    a. Revised reference for existing fence to remain
    b. Revised legend item “Perimeter Enviro Fence” to align with Erosion and Sediment Control Plan

Drawings - Landscape

1. L.1 – Landscape Plan
    a. The length of the wood privacy fence was reduced.
    b. The depth of concrete was clarified.
2. L.4 – Landscape Details

Question 1:

Please refer to specs section 01 40 00, 1.4.3 refers to cash allowance for third party testing & inspection as specified din section 01 21 13. However, there is no cash allowance for third party testing & inspection. Please advise

Answer 1:

A cash allowance of $75,000 has been included for unforeseen third-party testing and inspection services not otherwise identified in the Contract Documents. The allowance will be expended only upon written direction from the Owner and adjusted based on actual invoiced costs.

Question 2:

With reference to Specification Section 28 45 00 – Water Detection and Alarm, Article 2.1 – Manufacturers, please consider WASENS as an acceptable alternative manufacturer for the water detection and alarm system, including its HUB units, wireless flood sensors, rope sensors, and probe sensors, subject to compliance with the project specifications and approval by the Consultant.

Answer 2:

Refer to Addendum 4

Question 3:

Please refer to structural section details 3, 5/S500 shows key in the wall and shows two steps pour for the reduced wall thickness for exterior rigid insulation/stone ledge. Can we have monolithic pour to FFE and leave the rigid insulation/stone ledge formed?

Answer 3:

Refer to Addendum 4

Question 4:

Please refer to S203. Does section 13/S510 apply to all openings typical on all levels for the openings?

Answer 4:

Refer to Addendum 4.

Question 5:

Architectural section 2/A5201, 1/A5201 shows continuous angle and says refer to structural. Please advise which section and plan details show the angle details and advise if all exterior shelf and reveal angle required to be galvanized.

Answer 5:

Refer to Addendum 4.

Question 6:

Please advise if there will be BAS control. If yes, please provide manufacturer name.

Answer 6:

Refer to Addendum 4

Question 7:

Please advise if there are any union requirements.

Answer 7:

Refer to Addendum 4

Question 8:

Please refer to specs section 01 13 00 – Delegate Design Requirements. 3.2 Delegates design schedule, There are certain sections which don't require delegate design and it's not normal like for the section 09 21 16 – Gypsum board: for light gauge metal studs framing, section 26 56 13: Light poles, as usually designed by the project engineer, section 32 31 13 – wood fence, always designed by landscape consultants, Please advise.

Answer 8:

Refer to Addendum 4

Question 9:

We are looking to supply Canadian materials and products ... Can Windspec

and/or Commdoor Aluminum be considered as an alternate supplier for the curtain wall - windows - doors etc.?

Answer 9:

Refer to Addendum 4

Question 10:

On drawing E-100, it is not clear the size of Primary and Secondary Duct Banks. However, as per detail 1/E-102 , it shown as 4-4" DB2. So , we are following this detail for both Primary and Secondary duct banks.
Please confirm.

Answer 10:

Refer to Addendum 4

Question 11:

The specifications call for non-US products but the specified BRICK1 and the approved alternates are from the US. In addition, Brick2 is from Denmark but the approved equivalent is also from the US. Please confirm what alternate Canadian manufacturers you would like us to proceed with and please specify the products.

Answer 11:

Refer to Addendum 4

Question 12:

Specifications 07 21 00 - Page 5 of 10 states that Rigid Polystyrene Insulation is to be located at cavity wall near grade. Please confirm how high that would be or if it’s behind the stone base only and if that would be considered near grade.

Answer 12:

Refer to Addendum 4

Question 13:

Please provide specifications on the installation of stone that is 50mm thick. We are assuming that is mechanically anchored due to the thickness of the stone. Please confirm.

Answer 13:

Refer to Addendum 4

Question 14:

Please provide 1 week extension to the bid and extend the question period by 1 week.

Answer 14:

Refer to Addendum 4

Question 15:

Drawing S202 second level framing plan grid line A-B and 3-4. Please indicate the required size of the CLT panel. Size is not indicated in the specified location.

Answer 15:

Refer to Addendum 4

Question 16:

Could you please clarify which product and gauge the exterior soffit system requires?

Answer 16:

Refer to Addendum 4

Question 17:

Do we need to pay for construction fast-fence on site, if yes please provide value required

Answer 17:

Refer to Addendum 4

Question 18:

Site plan A0601 has waste collection staging area with note screen wall. please provide detail and material for installation of screen wall.

Answer 18:

A detail for the screen wall will be provided in a forthcoming addendum.

Question 19:

Would you please confirm Construction schedule as below based on Construction Management Plan?

Answer 19:

Revised Schedule below:

U/G Services: December 2026 – February 2027
Bldg. Construction: February 2027– December 2027
Occupancy Date: December 2027
Sidewalk & Trees: Spring 2028

Question 20:

Type L Copper Piping: For domestic water piping installed inside the building and aboveground, in sizes up to 100 mm (4 inches) in diameter, is Type L copper pipe acceptable, subject to compliance with the applicable plumbing code and approved fittings?

Answer 20:

No, Durham Region does not want copper type L and has required tyle K everywhere

Question 21:

PEX Piping Within Suites: Is PEX piping permitted for domestic hot and cold-water distribution within individual residential suites?
Please confirm/clarify acceptance of the above proposed materials and advise.

Answer 21:

Yes, PEX piping is permitted for domestic hot and cold water distribution within individual residential suites.

Question 22:

Please confirm if the on-site sidewalk construction is to follow detail 1/L.4? If yes, confirm if the concrete paving is 150mm thick or 130mm thick? The top image of detail 1/L.4 shows 150mm thick sidewalk whereas the bottom image calls out 130mm thick sidewalk.

Answer 22:

1/L.4 is correct for on-site sidewalks. The correct figure is 150mm depth. 130mm measurement is an error that will be corrected in the addendum.

Question 23:

Please confirm if tactile plates are required by the handicap parking space? If yes, clarify where and extent of tactile plates?

Answer 23:

There are no tactile plates to be used for accessible parking spaces.

Question 24:

Specification Section 04 20 00 – Request for Clarification / Revision
Please refer to Specification Section 04 20 00, Paragraph 1.5.2, which requires the Contractor to retain a licensed Professional Engineer to perform the services outlined in Paragraphs 1.5.2.1, 1.5.2.2, and 1.5.2.3.
This delegated design requirement is not typical practice for Division 04 masonry work, where the design professional generally specifies the masonry reinforcement requirements, including the type, size, and spacing of reinforcement.
We request that the delegated design requirement be removed and that the Contract Documents be revised to clearly indicate all required masonry reinforcement details, including the type, size, and vertical and horizontal spacing of joint reinforcement, wall ties, and other applicable reinforcing elements, as required for the project.
Please confirm whether this requirement can be revised accordingly.

Answer 24:

Please follow the project requirements.

Question 25:

Please extend the current RFI’s deadline Oct.16, 2026 has so far, we haven’t received responses to RFI’s and there may be further clarifications required once we receive an addendum.

Answer 25:

Refer to Addendum 4

Question 26:

Please refer to Domestic Supply chain Plan-Major Goods and Services, line item#2 for Masonry Materials (masonry blocks, masonry accessories). Please advise on below items:
a) As there is no structural masonry work. Cost of Exterior brick veneer and stone veneer to be included here?
b) Specified brick “The Belden Brick” and Endicott by Thames valley brick is from USA. Can you please consider an alternative Canadian made Canada brick or Brampton Brick?

Answer 26:

a) Yes
b) Alternative products will only be considered if the Bidder satisfies the requirements listed in Document 1 of 5, Article 1.7 and no later than 10 days prior to the bid closing date.

Question 27:

Can you please accept Romex wiring for this project?

Answer 27:

Alternative products will only be considered if the Bidder satisfies the requirements listed in Document 1 of 5, Article 1.7 and no later than 10 days prior to the bid closing date.

Question 28:

There is a CT04 tile in the Remarks column of Room Finish Schedule (CT4 Refer for enlarged suite plan for extend) this product it is not included in the Material and Finish Schedule. Please, clarify

Answer 28:

CT04 is not required. The Room Finish Schedule will be updated in a forthcoming addendum

Question 29:

There is a CT03 tile at Vanity Backsplash in the Remarks column of Room Finish Schedule; in the Material and Finish Schedule is CT01 wall tile WC Sink Backsplash. Please clarify.

Answer 29:

The Vanity Backsplash shall be provided as indicated in the Material and Finish Schedule (CT01). The Room Finish Schedule will be updated accordingly in a forthcoming addendum

Question 30:

Main door suite entrance threshold – it is not specified. Please, clarify and send us the specification.

Answer 30:

The 413S Threshold was specified for the entry suite doors

Question 31:

Please advise if Windspec for the curtain wall and doors in specs section 08 44 00, 2.1.3, 2.1.5 and Windows by Zenith/Falbo is acceptable per specification section 08 44 00, 2.1.4 including louvers.

Answer 31:

Alternative products will only be considered if the Bidder satisfies the requirements listed in Document 1 of 5, Article 1.7 and no later than 10 days prior to the bid closing date.

Question 32:

Section 08 71 00, 2.13 Low Energy Power Operators: Please confirm Micom SW800 low-energy swing operator (ANSI/BHMA A156.19) is an acceptable manufacturer for the 19 low-energy operators scheduled in Sets 02, 05, 08, 13, AL-01, AL-04 and AL-05. Micom is a Canadian manufacturer with local parts and service support. Product data is available on request.

Answer 32:

Micoms auto operators are 1/4hp and therefore not equal to the Hager 8300 series 1/3hp

Question 33:

Soil Characterization – Excess Soil
Has the Region completed a soil characterization assessment for the project to determine the quality and classification of excess soil to be removed from the site? If so, could the relevant reports and test results be provided for review?

Answer 33:

Refer to Addendum 4

Question 34:

S1001 Third-Party Testing Allowance
Has a cash allowance or contingency allowance been included in the project budget for the third-party integrated systems testing and commissioning required under CAN/ULC-S1001? If so, please confirm the amount allocated and whether the cost is to be carried by the contractor as part of the tender submission. Please also clarify who is responsible for coordinating and arranging the integrated systems testing, including the engagement of the qualified third-party testing agency and coordination of the various fire protection and life safety systems.

Answer 34:

A cash allowance of $75,000 has been included for unforeseen third-party testing and inspection services not otherwise identified in the Contract Documents. The allowance will be expended only upon written direction from the Owner and adjusted based on actual invoiced costs.

Also, the General Contractor shall be responsible for the coordination, scheduling, and successful completion of all Integrated Systems Testing (IST), including engagement of a qualified third-party testing agency where required. The Contractor shall coordinate all related trades and systems involved in the fire protection and life safety interfaces. All associated costs, testing, documentation, and retesting shall be included in the Contract Price unless otherwise noted in the Contract Documents.

Question 35:

Domestic Supply Chain Classification
If a supplier is an American-owned company but manufactures its products at a facility in Ontario, would those products qualify as Ontario-Made Goods or Canadian-Made Goods?
Could you also clarify whether the ownership or head office location of the supplier has any impact on the domestic content classification, or whether the classification is based primarily on the origin of the goods and where they are manufactured?

Answer 35:

Ontario-made-goods and Canadian-made-goods, refers to wholly manufactured / originated in Ontario or Canada or 51% of the total direct production/manufacturing cost incurred in Ontario or Canada, or labeled as “made in Canada” / “Product of Canada”.

Question 36:

Given the anticipated construction start in January, please confirm whether a cost allowance has been included for concrete half-load charges due to reduced delivery quantities during winter construction.

Answer 36:

No cash allowance has been included for concrete half-load charges or other winter-related delivery premiums. Bidders shall include in their tender price all costs associated with means, methods, sequencing, seasonal construction requirements, winter conditions, supplier premiums, delivery restrictions, half-load charges, and any other costs necessary to complete the Work in accordance with the Contract Documents. The Contractor is responsible for reviewing and accounting for all anticipated winter construction impacts in its bid.

Question 37:

Please confirm whether a cost allowance has been included for temporary winter heating during construction. If so, please identify the applicable allowance and any associated requirements.

Answer 37:

No specific allowance has been included for temporary winter heating. The Contractor shall include all costs associated with temporary heating, weather protection, and maintenance of required construction temperatures as necessary to complete the Work in accordance with the Contract Documents.

Question 38:

Please clarify if Vibration Monitoring & Pre-construction condition surveys are required and if there is a cash allowance?

Answer 38:

We have confirmed that the Town of Whitby requires the completion of Vibration Monitoring Programs and Pre-Construction condition surveys are required in accordance with the recommendations of the “Construction Vibration Zone of Influence Report” completed by EXP (June 2025). Applicant to provide provisions for such items in tender pricing.

Question 39:

Site Benchmark and Current Topographic Survey
Could you please confirm the following: Is there a usable benchmark on the property? The civil drawings reference benchmark 00819668302, elevation 101.580 m. Please provide the location and confirm whether a site benchmark remained following demolition.

Is a current topographic survey available following demolition and stripping? If so, please provide a copy showing current existing ground elevations across the entire site, including the building footprint, site servicing routes and service connection areas. If not, please advise whether any current ground elevations have been verified. Current elevations are needed to calculate excavation depths for the foundations, servicing trenches and other site servicing work.

Answer 39:

Please refer to attached Topographic Survey, prepared by Rouse Surveyors Inc (Feb 25, 2025). Benchmark 00819668302 Cosine Report attached. Per cosine report, Location Description:

WHITBY TWO STOREY YELLOW BRICK BLDG (WHITBY CENTIENNIAL BLDG) ON THE N.W. CORNER LOT OF ONTARIO ST AND CENTRE ST IN THE TOWN OF WHITBY, 1.1 KM NORTH OF THE JCT OF HWY 401 AND HWY 12 (BROCK ST) AT INTERCHANGE 67, 0.3 KM WESTERLY ALONG ONTARIO ST. TABLET IS SET HORIZONTALLY IN THE NORTH FACE OF THE MOST NORTHERLY OF FOUR STONE BUTTRESSES FACING CENTER ST, 16.2 M SOUTH OF THE N.E. BLDG CORNER AND 46 CM BELOW BRICKWORK.

Question 40:

The project specifications identify brick products manufactured by Belden Brick Company (USA) and Peterson Tegl (Denmark), as well as natural stone veneer supplied by A. Lacroix Granit (Quebec).
Please confirm whether alternative products from Canadian manufacturers would be acceptable for consideration, provided they meet the specified performance requirements, dimensions, textures, and overall design intent.
Proposed alternative manufacturers include:
• Brick: Brampton Brick and Canada Brick (Ontario)

• Natural Stone Veneer: Masonal Stone
If alternative products are acceptable, please advise whether equivalent products may be submitted for review and approval. The Architect is requested to confirm the acceptable colours and provide direction on the selection of brick and natural stone veneer to ensure consistency with the project's design intent.

Answer 40:

The brick and stone selections were established through an extensive heritage approval process and were subsequently reviewed and approved by the Heritage Committee. Bidders shall include the specified brick and stone products in their base bid.

Question 41:

Fire Protection Hazard Classification – Roof Area
Drawing M-404 indicates a Light Hazard classification for the roof area. However, NFPA 13 appears to require a Medium Hazard classification for this area based on the applicable occupancy and use. Please review and confirm the required hazard classification for the roof area.

Answer 41:

Quasar's interpretation of NFPA 13 is that the attic area is a light hazard classification since the attic is only used for access to rooftop mechanical equipment and for maintenance of some fans and ductwork. Rooftop equipment is all located on a roof open to above.

Question 42:

Drawing M-404 indicates a 4-inch fire protection main and control valve serving the roof structure, whereas 2-inch mains and control valves are indicated on the

other floors. Please confirm that the 4-inch sizing is intentional and provide the rationale for the difference in sizing.

Answer 42:

Full detailed fire protection design is not in Quasar's scope, performance based drawings are only being provided. Contractor is responsible for detailed sprinkler piping design and hydraulic calculations subject to Quasar's review, pipe sizing can be modified as long as hydraulic calculations provided can demonstrate that the system works and applicable codes are met.

Question 43:

Sprinkler Installation Location – Roof Structure
Drawing M-404 indicates sprinkler protection at the roof structure. Please confirm whether the intent is to install the sprinklers within or above the roof trusses. If so, please clarify the design rationale and confirm whether this arrangement is required due to the absence of a fire-resistance-rated (FRR) ceiling assembly.

Answer 43:

See response #41 above

Question 44:

The shower floors are floor tile PCT02 or shower pan.

Answer 44:

Shower pan shall be provided. Refer to spec section 22 42 00

Question 45:

Video Surveillance Server and Storage Redundancy
Reference: Page 1976, Section 1.3.2
The specification states:
“The Video Surveillance System shall be designed on a distributed processing architecture employing remote cameras and operator workstations connected to a redundant central server and storage solution.”
Please clarify if a redundant central server and storage requires a secondary complete server and storage to be available for failover should the primary recording server fail.

Answer 45:

A redundant/secondary server is not required.

Question 46:

Audio-Visual Fire Alarm Integration
Section 27 41 00 requires the Audio-Visual system to interface with the building fire alarm system for audio muting during a fire alarm event.
Please confirm the division of responsibilities between the Audio-Visual contractor and the fire alarm contractor. Specifically:

a) Will the fire alarm contractor provide the required supervised output, dry contact, relay, interface wiring and fire alarm programming?
b) Will the Audio-Visual contractor’s responsibility be limited to connecting the AV system to the fire alarm interface provided by the fire alarm contractor?
c) Will integrated testing and verification be completed jointly by the AV and fire alarm contractors?

Answer 46:

a) The fire alarm contractor will provide the required supervised output, dry contact, relay, interface wiring and fire alarm programming.
b) In the context of the fire alarm interconnections the AV contractors' responsibility is limited to the fire alarm interface provided by the fire alarm contractor.
c) Integrated testing will be completed jointly. The Audio-Visual contractor is not licensed to modify, program or perform work within the fire alarm system.

Question 47:

RDL ST-SSR1 Fire Alarm Audio-Muting Interface
The specifications identify the Radio Design Labs ST-SSR1 audio-muting switch and associated PS-24AS power supply.
Please confirm whether the ST-SSR1 and PS-24AS are to be supplied and installed by the Audio-Visual contractor or the fire alarm contractor.
If these devices are included in the Audio-Visual contractor’s scope, please confirm that the fire alarm contractor will provide the required fire alarm relay or dry contact and complete all fire alarm-side wiring, programming and verification.
The Audio-Visual contractor would then connect the AV system to the provided interface and participate in integrated testing.

Answer 47:

The AV contractor is to supply the audio muting device.

The fire alarm contractor will provide the required supervised output, dry contact, relay, interface wiring and fire alarm programming.

Question 48:

Audio-Visual Backboxes
Please clarify the division of responsibilities for AV backboxes and associated infrastructure:
1. Are all AV-specific backboxes to be supplied by the Audio-Visual contractor or by the General Contractor/electrical contractor?
2. Will the General Contractor/electrical contractor install the AV backboxes, conduits, raceways, and pathways?
3. Are standard device boxes, junction boxes, and pull boxes included in the General Contractor/electrical contractor's scope?

Answer 48:

1. The Electrical contractor is responsible for conduits, raceway, pathways and backboxes.
2. The Electrical contractor is responsible for conduits, raceway, pathways and backboxes.
3. The Electrical contractor is responsible for conduits, raceway, pathways and backboxes.

Question 49:

Replacement Equipment Within 24 Hours
The specifications reference the provision of replacement equipment within 24 hours.
Please clarify the intent and extent of this requirement:

a) Does this require the contractor to provide temporary loaner equipment within 24 hours while the original equipment is being repaired?
b) Does the requirement apply only to equipment considered critical to system operation?

c) Is permanent replacement of defective equipment required within 24 hours?
d) Does the 24-hour period include weekends and statutory holidays?
e) Is this requirement applicable during construction, commissioning, the warranty period or all three?
f) Is an onsite spare-equipment inventory required as part of the contract?

Answer 49:

a) Yes
b) Yes
c) Yes
d) No
e) Warranty Period
f) Yes

Question 50:

Blu-ray Player Supply
Section 27 41 00 includes a Blu-ray player as part of the Amenity Room Audio Visual system.
Please confirm whether the Blu-ray player is:
• Supplied by the Owner and installed by the Audio-Visual contractor, or
• Supplied and installed by the Audio-Visual contractor.
If contractor-supplied, please provide the required manufacturer, model or minimum performance requirements.

Answer 50:

Contractor supplied, Sony, Samsung or Toshiba consumer models are acceptable

Question 51:

Proposed Substitution for Kramer Equipment
Section 27 41 00 identifies several Kramer products as the basis of design. Please confirm whether a complete, functionally equivalent Audio-Visual solution using Crestron and other recognized Tier 1 manufacturers may be proposed as an approved equivalent.

Answer 51:

Alternative products will only be considered if the Bidder satisfies the requirements listed in Document 1 of 5, Article 1.7 and no later than 10 days prior to the bid closing date.

Question 52:

Proposed Audio-Visual Equipment
Please confirm whether the following products may be submitted as approved equivalents:

- Crestron DM-NAX-AMP-X300 networked audio amplifier
- Crestron DM-NVX-360 AV-over-IP encoder/decoder
- Crestron TSW-1070-W-S touchscreen
- Crestron CP4N control system
- Crestron SAROS PD6T pendant speaker
- NETGEAR M4250-26G4XF-PoE+ managed network switch
- Crestron MC4 compact control system
- Crestron IRP2 infrared emitter probe

Answer 52:

No, the Region is no longer accepting ‘alternative product’ proposals as the deadline for requesting ‘equivalent products’ has expired, please refer to Part 1, Article 1.7.

Question 53:

Audio-Visual Onsite Training Requirement
The specifications require two onsite training sessions, each lasting a minimum of two hours and covering system operation, signal routing, troubleshooting, and preventive maintenance.
Please confirm that these sessions are included in the AV contractor’s scope and advise of any additional requirements, including:

a) Number and type of attendees.
b) Whether sessions must be held on separate dates
c) Required timing relative to substantial performance
d) Printed or electronic training materials
e) Recorded training sessions
f) Manufacturer-led training
g) Additional training sessions

Answer 53:

Training is part of the AV contractors scope.

a) Attendees will consist of client/operations/city staff, number TBD
b) Sessions can be held on the same date, this must be coordinated with operations/city staff.
c) The AV systems must be fully functional during training, timing to be coordinate with client client/operations/city staff after system is functional.
d) Electronic is preferred

e) Not required
f) Not required
g) Not required

Question 54:

In-Suite Telecommunications Cabling
Please confirm whether all telecommunications cabling within the residential suites will be supplied and installed by Bell, Rogers, or another service provider.

Answer 54:

In suite cabling, pathways and P3000/media-panel are the responsibility of the bidder/contractor and to be included for.

Question 55:

Primex P3000 Communications Panels
Please confirm whether the Primex P3000 residential communications panels, including associated conduits and pathways, will be supplied and installed by others.

Answer 55:

In suite cabling, pathways and P3000/media-panel are the responsibility of the bidder/contractor and to be included for.

Question 56:

Telecommunications Pathways and Supports
Please identify the trade responsible for supplying and installing telecommunications conduits, cable trays, J-hooks, and other non-continuous cable supports.

Answer 56:

The electrical contractor is responsible for pathways and cable supports.

Question 57:

MDF Fire-Rated Plywood
Please identify the trade responsible for supplying and installing the fire-rated plywood backboard in the MDF.

Answer 57:

Unable to decipher which section you are referring to – therefore unable to answer question.

Question 58:

Cabinet Grounding and Bonding
Please identify the trade responsible for grounding and bonding the IT/network and AV cabinets.

Answer 58:

Division 27 is responsible for grounding and bonding the IT/network and AV cabinets

Question 59:

MDF Wall-Mounted Cabinets
Please identify the trade responsible for supplying and installing the MDF wall-mounted cabinets and provide the required dimensions, rack-unit capacity, and specifications.

Answer 59:

Unable to decipher which section you are referring to – therefore unable to answer question.

Question 60:

Please confirm if the on-site sidewalk construction is to follow detail 1 drawing L.4? If yes, confirm if the concrete paving is 150mm thick or 130mm thick? The top image of detail 1/L.4 shows 150mm thick sidewalk whereas the bottom image calls out 130mm thick sidewalk.

Answer 60:

Detail 1/L.4 is correct for on-site sidewalks. The correct figure is 150mm depth. 130mm measurement is an error that will be corrected in the addendum.

Question 61:

Please confirm if we can use granular A gravel as sidewalk base gravel? Detail 1/L.4 specifically calls out 19mm crusher run limestone as base gravel.

Answer 61:

Granular A is acceptable for the sidewalk base.

Question 62:

Please confirm if any reinforcing is required in the pedestrian sidewalks? If yes, clarify type and spacing (if required).

Answer 62:

There is no reinforcing required in the pedestrian sidwalks.

Question 63:

Confirm if we need to include for HL3F asphalt paving on this project? Section 32 00 00A makes reference to HL3F asphalt for surface for driveways, boulevards...but none of the details call for HL3F. If yes, clarify where to include for HL3F asphalt surface course?

Answer 63:

Bidders are not required to include HL3F asphalt paving in their tender. The reference to HL3F within Section 32 00 00A does not apply and has been removed from the specifications. Reference to HL8 (PGAC 64-28) has also been removed.

Question 64:

Confirm no asphalt curbs are required at catch basins? Section 32 00 00A makes reference to asphalt curbs at catch basins but no asphalt curbs are called out on the plans. If yes, please clarify?

Answer 64:

As standard practice, asphalt curbs are required at catch basin installations within the right-of-way during restoration works and shall remain in place until the permanent concrete curb and gutter has been reconstructed. While not specifically shown on the drawings, this requirement is intended to maintain positive drainage to the catch basin during the interim restoration period.

Question 65:

AV Cabinets
Please identify the trade responsible for supplying and installing the AV cabinets and provide the required dimensions, rack-unit capacity, and specifications

Answer 65:

The AV contractor is to supply these devices.

Question 66:

Cabinet Accessories
Please confirm the required cabinet accessories, including PDUs, equipment shelves, and cable-management components, and identify the trade responsible for supplying them.

Answer 66:

The AV contractor is to supply these devices.

Question 67:

Telecommunications Riser
Please identify the location and routing of the telecommunications riser serving the building.

Answer 67:

ICAT riser is in the Electric, in ELEC Closets 117, 217 and 317.

Question 68:

Parking-Lot Camera Connectivity
Please confirm whether the pole-mounted parking-lot cameras require fibre-optic connectivity or whether extended-reach copper cabling is acceptable.

Answer 68:

No, the Region is no longer accepting ‘alternative product’ proposals as the deadline for requesting ‘equivalent products’ has expired, please refer to Part 1, Article 1.7.

Question 69:

Sleeves, Penetrations, and Firestopping
Please identify the trade responsible for supplying and installing conduit sleeves and penetrations and for firestopping penetrations associated with Division 27 cabling.

Answer 69:

Division 26 is responsible for conduit, pathways, sleeves etc.

Question 70:

ISP Demarcation Point
Please identify the ISP demarcation point and confirm the required interface and division of responsibilities between the service provider and the building telecommunications infrastructure.

Answer 70:

The demarcation point is in ELEC & COMMS room B101 as shown on drawing T-700.

Question 71:

Structured Cabling Manufacturer
Section 27 10 00 identifies Belden as the specified structured cabling manufacturer and requires a certified manufacturer-supported solution. However,

other Division 27 sections also reference CommScope and Panduit as acceptable manufacturers for the copper and fibre cabling infrastructure. Please confirm whether an end-to-end structured cabling solution from CommScope including copper and fibre cabling, connectivity, patch panels, fibre enclosures, patch cords, testing, certification, and the applicable manufacturer warranty, would be accepted as an approved equivalent.

Answer 71:

Alternative products will only be considered if the Bidder satisfies the requirements listed in Document 1 of 5, Article 1.7 and no later than 10 days prior to the bid closing date.

Question 72:

Owner-Supplied Network Equipment
Please confirm that all network equipment to be supplied by the client.

Answer 72:

Active equipment (except security switches and servers) are to be supplied by the client as per Section 27 10 00 (1.2.1) and Section 27 21 33.

Question 73:

Confirm we do not have to include for HL8 asphalt infill (300mm width) for concrete curbs completed after base asphalt. Section 32 00 00A makes reference to this item but not shown on any drawings.

Answer 73:

Asphalt infill adjacent to concrete curbs will only be required where the curb is installed after placement of the base asphalt. In such cases, the asphalt infill shall be provided in accordance with Section 32 00 00A. Contractors are

responsible for determining their preferred construction sequence. The specification is included to address circumstances where curb installation occurs after paving and does not constitute a mandatory construction methodology. The sequencing of asphalt works is at the Contractor's discretion. Bidders shall account for any costs associated with their proposed construction methodology, whether completed in a single mobilization or multiple mobilizations.

Question 74:

Please confirm if the on-site top and base asphalt can be completed all in 1 mobilization? Or, must we include for separate mobilizations for top and base course asphalt installation?

Answer 74:

The sequencing of asphalt works is at the Contractor's discretion. Bidders shall account for any costs associated with their proposed construction methodology, whether completed in a single mobilization or multiple mobilizations.

Question 75:

Please confirm if tactile plates are required by the handicap parking space? If yes, clarify where and extent of tactile plates?

Answer 75:

There are no tactile plates to be used for accessible parking spaces.

Question 76:

Domestic Supply Chain Plan - Major Goods and Services: Would the Owner consider allowing bidders to submit the Domestic Supply Chan Plant - Major Goods and Services breakdown within 1 hour following the bid closing time?

Closing time is very busy and this will allow the contractors to focus on pricing and after we will have more time to produce Domestic Supply Chain Plan.

Answer 76:

No, the DSCP needs to be provided a bid close

Question 77:

Drawing A4204 detail 1, please indicate whether the handrail on the interior of stairs A and B is continuous. The drawing shows the handrail as continuous, but there is no note explicitly stating such. If the handrail is to be continuous please indicate the preferred splice type.

Answer 77:

The handrail is continuous for both Stair A & Stair B. The splice type will be added in the specification in a forthcoming addendum

Question 78:

Drawing A4202, A4201 - The drawings show the wall rails as continuous, but the note stating this only applies to stair B. Wall rails that are to be continuous, please indicate which ones and the preferred splice.

Answer 78:

The railing shall be continuous for both Stair A and Stair B

Question 79:

Please provide 1 week time extension to allow contractors sufficient time to review all the contract documents.

Answer 79:

Refer to Addendum 4

Question 80:

1. Please confirm suite doors have hollow metal frame as shown on elevation 10/A8301, otherwise provide details and specify materials accordingly.
2. Please specify the intent for inside suite door frames and casings and provide details accordingly. Is it hollow metal or plastic laminate plywood as noted on suite door schedule on dwg A6120?
3. Section 06 20 00, subsection 2.4.1.11 mentions Glazed wood screens. Please specify details for Glazed wood screens and their location.
4. Is the intent for casework to be wood veneer as Note 18 on dwg A8100? Section 09 06 00, Material and Finishes Schedule states white melamine for interior of cabinets.
5. Please provide details for suite closets.
6. Is the intent for Plastic Laminate window sills to have solid core as mentioned in Section 06 20 00, subsection 2.4.13 or plywood core?
7. Please specify the extents for FRP panels in Waste Rm #109.
8. Please confirm the stated “millwork at waste bin” at Section 06 20 00, subsection 2.4.1.13 is MW110 on dwg A8301, otherwise specify the location.
9. Please specify the detail for F1A and F2A door frames on dwg A6102.
10. Please confirm the suite windows do not have wood casings.
11. Please specify the core material for plastic laminates. Is it veneer core, MDF or particleboard?
12. Please specify where in the project High Density Fibreboard (HDF) core and panels are required as noted in in Section 06 20 00, subsection 2.1.9?

Answer 80:

1. Suite doors shall be provided as specified in section 08 14 16, 2.1.4. The note on elevation 10/A8301 will be revised in a forthcoming addendum
2. Interior doors shall be provided as specified in section 08 14 16, 2.1.3. The door schedule will be revised as required in a forthcoming addendum
3. Glazed wood screens are not proposed in this project.
4. Note 18 on dwg A8100 does not refer to millwork finishes. Please clarify the question. Casework/Millwork Finishes shall be provided as per schedule on A8100. Interior of cabinets shall be provided as per Material and Finish Schedule.
5. Refer to Spec Setion 08 14 73 Sliding Closet Doors
6. Interior window sills shall be provided as WD01. Section 06 20 00, 2.1.4
7. FRP panels shall be provided on all walls to the u/s of ceiling. A note to clarify the extents will be added in the Room Finish Schedule in a forthcoming addendum
8. Yes. Refer to MW110
9. Response to follow
10. Suite windows do not have wood casing. Refer to 7/A5301 for typical window jamb detail.
11. The core material will depend on the application. Refer to the specifications.
12. HDF is proposed in the stairs (refer to 2/A4204)

Question 81:

10/A8201 Notes the top shelf is 19mm thick while the shelf above rod is 2 - 19mm shelves together, is this correct or is one 19mm shelf acceptable?

Answer 81:

1 shelf is acceptable. The detail callout will be revised to S3 in a forthcoming addendum

Question 82:

Many drawer banks show a shallow first drawer, please confirm the height of this drawer?

Answer 82:

The shallow first drawer represents a pull-out counter extension, which is required for barrier free units. Spec Section 06 20 00 will be updated in a forthcoming addendum.

Question 83:

3/A8201 notes a few 19mm gables. Are applied gables required at each of these notes or is it acceptable to just have a finished gable as part of the cabinet? This elevation doesn't draw a gable at all spots the arrows are, therefore the sink cabinet and bank of drawers would shrink. If this is for symmetry, don't leave out the fact that a 25mm filler would typically be required where cabinet meets wall.

Answer 83:

It is acceptable to have a finished gables as part of the cabinet. In the drawings there is 19mm space allotted for gables even if they are not graphically depicted with solid line. The cabinets are all drawn true to the tagged sizes. Other than minor reduction at cabinets next to walls as required, there should be no shrinkage of any elements.

Question 84:

For domestic water piping installed inside the building and aboveground, in sizes up to 100 mm (4 inches) in diameter, is Type L copper pipe acceptable, subject to compliance with the applicable plumbing code and approved fittings?

Answer 84:

No, Durham Region does not want copper type L and has required tyle K everywhere

Question 85:

Is PEX piping permitted for domestic hot and cold-water distribution within individual residential suites?

Answer 85:

Yes, PEX piping is permitted for domestic hot and cold water distribution within individual residential suites.

Question 86:

The door schedule calls for all suite entries and interior suite doors to have PLAM faces. Typically we do not see PLAM used for interior suite openings. Please confirm if PLAM should actually be used for these doors or if they should be paint grade.

Answer 86:

PLAM shall be used for both suite entries and interior suite doors as indicated in the door schedule. The PLAM finish shall be provided in accordance with the Material & Finish Schedule

Question 87:

Please confirm if interior suite doors should be hollow-core or solid-core, and if they should be 1 3/8 or 1 3/4 thick.

Answer 87:

Please refer to Spec Section 08 14 16, 2.1.3

Question 88:

The door schedule calls for PLAM wood frames inside the suites. We assume this is incorrect and that the frames will be painted, please confirm.

Answer 88:

PLAM shall be used for both suite entries and interior suite doors as indicated in the door schedule. The PLAM finish shall be provided in accordance with the Material & Finish Schedule

Question 89:

The door schedule calls for suite entries to be pre-hung with a 20-minute rating. Typically we see hollow-metal frames used for suite entries. Please confirm the frame material. If you want the appearance of wood trim for the suite entries, flush-fit frames can be used, allowing wood trim to be applied on top.

Answer 89:

Suite entry doors shall be provided in accordance with 08 14 16, 2.1.4

Question 90:

The door schedule lists the stairwell doors as plain slabs, but typically we see narrow-lites used for all stairwell doors. Please confirm if lites are required for these doors.

Answer 90:

Narrow-lites are not required for the door panel. Sidelites have been provided instead.

Question 91:

The specified manufacturer's PVC-free polyester solar screen is 2% openness, and its 1% screens are vinyl blends. Please confirm whether a 2% PVC-free screen is acceptable, or whether 1% openness takes priority over PVC-free?

Answer 91:

It is acceptable to have 2% openness with a PVC-free solar shade. The related spec section will be updated in a forthcoming addendum

Question 92:

Please provide soil characterization report for this project. We need to know if soil is contaminated so that we can determine disposal costs. Alternatively if soil characterization report is not available please provide soil disposal allowance.

Answer 92:

Refer to Addendum 4

Question 93:

is Appendix 12 - furniture specification part of base bid or i for information only.
is Appendix 13- appliance schedule part of base bid or for information only
please advise

Answer 93:

Appendix 12 & Appendix 13 are part of the base bid.

Question 94:

Could you please clarify which product and gauge the exterior soffit system requires?

Answer 94:

Section 07 40 25 can be deleted in its entirety.

Question 95:

The specified manufacturer's PVC-free polyester solar screen is 2% openness, and its 1% screens are vinyl blends. Could the consultant confirm whether a 2% PVC-free screen is acceptable, or whether 1% openness takes priority over PVC-free? Our price covers either option.

Answer 95:

It is acceptable to have 2% openness with a PVC-free solar screen, The related spec section will be updated in a forthcoming addendum

Question 96:

Please provide make and model numbers for commercial laundry and washers on level 1.

Answer 96:

Refer to attachment forming part of Addendum 5.

Question 97:

Please refer to appliance schedule issued in Add#1. Please advise us on below items:
A) Specified, Summit won't give price for Range Hood (HOOD-1and HOOD-2). Could you please consider an alternative from Broan range hood?
B) Can you please consider an alternative from LG in lieu of specified cooktop CKTP-2?
C) Can you please consider alternative equivalent Range (RANGE-2 for Non-BF Suites) from LG in lieu of specified Whirlpool?

Answer 97:

Alternative products will only be considered if the Bidder satisfies the requirements listed in Document 1 of 5, Article 1.7 and no later than 10 days prior to the bid closing date.

Question 98:

Please refer to Section 08 71 00, 2.13 Low Energy Power Operators. Could you please consider Rhino Ado7000 Series as an alternative to specified.

Answer 98:

This is a medium duty operator and is not for high traffic areas.

Question 99:

06 20 00 - Soft-close hinge is not available with a 170° maximum opening. The maximum available opening with the soft-close feature is 125°. Additionally, the

soft-close feature for this hinge application more than doubles the hardware cost. Clarification requested: Will 170° self (spring) close hinges be accepted?

Answer 99:

This hardware will be updated in a forthcoming addendum.

Question 100:

Is the electrical contractor selecting the suite metering or is the owner selecting the suite monitoring as the water needs to be monitored as well?

Answer 100:

The Region will select the suite metering

Question 101:

TV, Telephone, Data outlets are missing in suites, is this all wireless? Has a provider been selected

Answer 101:

Typical suite details including the wireless electrical locks are found on drawing T-600

Question 102:

Will there be access control devices (card readers) or security cameras?

Answer 102:

Wired access control and cameras are on drawings T-300 through T-303, the typical suite details including the wireless electrical locks are found on drawing T-600

Question 103:

Will there be a cash allowance for hydro capital costs? Is the owner or GC responsible for temp power connection costs through the utility provider?

Answer 103:

A cash allowance of $350,000 has been included for hydro capital costs associated with the permanent utility service. The allowance will be adjusted to actual costs upon receipt of finalized utility quotations. The Contractor shall include all costs associated with temporary power required for construction.

Question 104:

Is data required at the future EV charging stations? If so, an additional conduit will need to be included.

Answer 104:

Future EV charging stations are expected to utilize cellular communications.

Question 105:

Are there any fire dampers that need to be controlled by the fire alarm?

Answer 105:

The makeup air supply duct has fire-smoke dampers on every floor, these will be connected to fire alarm. Please refer to drawings wherever fire-smoke dampers are shown

Question 106:

Is there any mechanical equipment that needs to be shut down on fire alarm initiation?

Answer 106:

Please refer to control sequences on sheets M-700 and M-701 for information on any equipment that shuts down during fire alarm.

Question 107:

As we discussed earlier regarding this project, the construction fence parallel to centre street will need to be temporarily moved during the building excavation, stockpiling and backfilling activities to facilitate the work and provide better access to the site.
Please note that, due to the limited space available for stockpiling the excavated native soil for reuse as backfill, the excavation and backfilling works will need to be carried out in two phases. This will allow the excavated soil to be temporarily stockpiled in the available area and reused for backfilling once the relevant phase of excavation is completed.
Please be advised that this phased approach may impact the concrete pouring schedule and the overall construction sequence.

Answer 107:

The Contractor shall be responsible for all site logistics, sequencing, temporary fencing relocations, excavation, stockpiling, and backfilling operations required to complete the Work. Any temporary fence relocation shall be coordinated with the Region and applicable authorities as required.

Question 108:

1. Power supplies: Section 08 71 00 lists Hager power supplies (2908–2911) in several sets, while Section 28 says the security contractor supplies power supplies. Who supplies the supplies at each opening? Do the supplies in Sets 02, 05 and AL-01 also power the door operators?
2. Door contacts and request-to-exit: Please confirm that door position switches,

PIR egress sensors and request-to-exit push buttons are Division 08. The security contractor would only terminate them to the controllers.
3. Credentials: How many, in what format (card, fob or mobile), and are staff credentials included?
4. Badge printer: Is a badge printer required? Section 28 describes badge printing through a print server. If one is required, who supplies it, and is there a preferred model?
5. Server: Who supplies the access control server (hardware or virtual)?
6. Server room location: Please state the exact location of the server room where the access control server and head-end equipment will be installed. Please also confirm that it is provided with power, cooling and network connectivity.
7. Workstations: Are monitoring workstations supplied by the Owner or the security contractor, and how many?
8. Monitoring location: Section 28 refers to an LTC, a 2nd floor RHA workstation and a SOC Where is monitoring located for this building?
9. Network: Does an existing Owner network and ACS VLAN exist at this site, or is a new one required?
10. Doors added to the SMS: Several hardware sets state -Door is monitored by access control system, while other electrified doors (for example the suite doors and the operator-only doors) do not. Please confirm that only the doors described as monitored are to be added to and programmed in the SMS, and that all other electrified doors are to be installed only, with no SMS programming.
11. Universal washrooms: E-832 shows emergency call systems on Levels 1 and 3, but the schedule has only D105. Which hardware set applies to Level 3, and who supplies the emergency call components?
12. Maglocks: E-831 (5) and E-850 (2) show maglock rough-in, but the schedule has none. Are any maglock doors required?
13. Elevators: Based on the access control specification, readers are required for all elevators. Please clarify whether readers are required at each level (landing) or inside the elevator cabs.

14. CCTV and intrusion: Are any CCTV, intrusion or duress devices required? The legend shows symbols, but no plans do.
15. Intercom: The plans show an intercom at vestibule 101, and Section 28 mentions an intercom icon at alarm locations. Should the intercom be integrated with the access control system? If so, who supplies the intercom equipment and what is the integration scope?

Answer 108:

1. The Hager power needs to be used for all Hager electrified devices for warranty purposes.
2. Response to follow
3. Credentials are card and fob format, 100 of each type, staff credentials are to be included.
4. Badge printer is to be supplied by contractor, magicard 600 or equivalent.
5. Access control is to connect/integrate with the client access control server.
6. Server room is ELEC & COMMS room B101, power, cooling and connectivity is provided.
7. One monitoring station is required to be provided by contractor
8. Response to follow
9. This is a new build, the client does have an existing ACS server.
10. Suite and wired access control doors require SMS programming, universal washrooms do not.
11. Door 301 per door schedule does not show an ADO is required. Hager to supply emergency call components.
12. No maglock provided in the building
13. Access control is required in the elevator cabs.
14. Access control is on T series drawings, no intrusion or duress is required.
15. Entry intercoms are to be integrated with access control to allow entry doors to be remotely opened, intercom is by division 28.

Question 109:

Please advise us of the duration of the half-load restriction for Region of Durham.

Answer 109:

Refer to Answer #36 above.

Question 110:

Please advise us what manufacturers to consider for winter heat admixtures for weather mix for winter concrete work?

Answer 110:

need to comply with A23.1/A23.2 and the specifications. We don’t provide specific products

Question 111:

On landscape drawing L1, there's a note that reads: Asphalt (see civil) with high albedo asphalt surface treatment - Streetbond SR (colour:slate). There is no mention of this in the civil drawings, and no specification has been provided. Please provide a specification for this item.

Answer 111:

The Streetbond SR is a surface application. Specification to be included with addendum 1. Note that coating coverage rate should be equal to that of a residential driveway.

Question 112:

1. Please identify the door frame detail and confirm the material for the following:
- Doors of common areas

- Suite entry doors
- Interior suite doors

2. Given the number of details, we kindly ask for an extension for the project.
3. Please specify ESF01 in detail 7/A5600.
4. Please confirm the material for wood slat walls, is it white oak veneer or plastic laminate as noted in Section 06 20 00, subsection 2.4.15?
5. Please confirm the bench shown at Staff Washroom #301 on dwg 11/A4402 has the same detail as lobby bench MW111.

Answer 112:

1. Please refer to the Door Schedule and to details on sheet A6100 & A6101
2. Refer to Addendum 4
3. Epoxy Floor System coved base
4. The material for the wood slat walls shall be white oak veneer (WD01). The spec section will be updated in a forthcoming addendum
5. The bench will be included as part of Appendix 12. (Furniture Specifications) in a forthcoming addendum

Question 113:

Please refer to Level 1 framing on S201. It refers to typical details for typical frost slab per PD-C-001 on S102. This detail shows reinforced interior slab on grade with reinforcement. Frost slab shows continuous dowels form slab on grade which is not the case here. Should we drill holes and epoxy dowels into the slab on grade? Please advise.

Answer 113:

Unable to decipher which section you are referring to – therefore unable to answer question.

Question 114:

Please provide TOF or U/S of footings for unexcavated areas in relation with geotechnical report same as give for basement portion on foundation plan S200.

Answer 114:

top of footing is -275 from the basement floor elevation throughout

Question 115:

Please confirm if bid closing extends from current closing date Oct.30, 2026 as it may take time to answers RFI's, then the construction start date also push back accordingly or not.

Answer 116:

Refer to Addendum 4

Question 117:

The room finish schedule indicates vanity backsplash for the common area and suite bathrooms; however, elevations are not available to determine the extent. Please clarify and specify the required height and extent of the vanity backsplash for bathrooms.

Answer 118:

Please refer to A4400. The types of tiles are identified in a color coded legend and shown accordingly on the enlarged plans.

Question 119:

Please refer to floor assemblies, FL2a, FL2b and FL2c. Floor assemblies and noticed the current design calls for a 40mm cast-in-place concrete topping over a

25mm acoustic isolation mat on the mass timber floors.

Would there be an opportunity for us to price a cementitious self-leveling underlayment/topping system as an alternative to the concrete topping?

We do a significant amount of this type of work on multi-family and mass timber construction. A pumped cementitious system can offer some advantages over conventional concrete, including reduced dead load, thinner assemblies where required, significantly better floor flatness, high daily production and a finished surface that's ready to receive flooring without having to come back and correct the concrete afterward. We can also incorporate the acoustic mat into a complete tested assembly.

Answer 119:

Alternative products will only be considered if the Bidder satisfies the requirements listed in Document 1 of 5, Article 1.7 and no later than 10 days prior to the bid closing date.

Question 120:

There are a few canopies on the building, I’m not able to find a canopy roof assembly. Is this information available anywhere? In the detail drawings it looks like it is listed as FL2b which would be a floor assembly. Is this in our scope of work?

Answer 120:

Please refer to detail 1 & 2 on sheet A5203

Question 121:

Should we add shoring and dewatering costs in 02 00 00 Existing Conditions?

Answer 121:

No for shoring. Refer to addendum 4

Question 122:

The specified manufacturer's PVC-free polyester solar screen is 2% openness, and its 1% screens are vinyl blends. Please confirm whether a 2% PVC-free screen is acceptable, or whether 1% openness takes priority over PVC-free?

Answer 122:

It is acceptable to have 2% openness with a PVC-free solar screen, The related spec section will be updated in a forthcoming addendum

Question 123:

Please confirm type of specified material for the staircase components; riser/tread/stringer for Stairwell A/B. Information not noted on Architectural or Structural Plans. Also, please confirm the strongback material specifications and any adhesives and additional structural fasteners.

Answer 123:

Material and fasteners shown in CD-022 on S104.

Question 124:

Is the electrical contractor selecting the suite metering or is the owner selecting the suite monitoring as the water needs to be monitored as well?

Answer 124:

The Region will select the suite metering

Question 125:

TV, Telephone, Data outlets are missing in suites, is this all wireless? Has a provider been selected?

Answer 125:

The typical suite details are found on drawing T-600, the contractor is to provide the in-suite media enclosure, pathways and cabling

Question 126:

Will there be access control devices (card readers) or security cameras?

Answer 126:

Please refer to the ICAT drawings and Division 28 specifications.

Question 127:

Will there be a cash allowance for hydro capital costs? Is the owner or GC responsible for temp power connection costs through the utility provider?

Answer 127:

Future EV charging stations are expected to utilize cellular communications.

Question 128:

Is data required at the future EV charging stations? If so, an additional conduit will need to be included.

Answer 128:

Future EV charging stations are expected to utilize cellular communications.

Question 129:

Are there any fire dampers that need to be controlled by the fire alarm?

Answer 129:

The makeup air supply duct has fire-smoke dampers on every floor, these will be connected to fire alarm. Please refer to drawings wherever fire-smoke dampers are shown

Question 130:

Is there any mechanical equipment that needs to be shut down on fire alarm initiation?

Answer 130:

Please refer to control sequences on sheets M-700 and M-701 for information on any equipment that shuts down during fire alarm

Question 131:

Reference: A4301 Section 7; Spec 05 50 00 2.3.9.5
Section 7 shows the pit ladder but not its length, width or rung spacing. A4301 shows the pit floor 1524 below L1, and spec 2.3.9.5 requires pit ladders to extend 1220 above finished floor. Please confirm the ladder extends 1220 above the L1 finished floor (approx. 2744 overall), and confirm ladder width, rung spacing and stand-off from the pit wall.

Answer 131:

Overall design of elevator pit ladder to comply with code requirements (ASME A17.1/CSA B44 safety code). Section 05 50 00 has been amended accordingly

Question 132:

Reference: A4301 Section 7
Section 7 does not indicate the fastener type for the ladder brackets into the concrete pit wall or into the stud wall above L1. Please confirm the fastener type at each substrate.

Answer 132:

Please follow the specifications requirements, including engineering requirements

Question 133:

Reference: A4206 Details 1 & 2; A1403
Details 1 and 2 show the Mech Rm 305 ship's ladder with no dimensions. Only the L3
(6300) and T/O L3 (9350) datums are given, so length and run can only be scaled. Please confirm:
- Distance from the west wall (grid 3) to the foot of the ladder Offset from the north exterior wall
- Top exit elevation (top of hatch curb)
- Ladder angle, number of risers and riser height

Answer 133:

Please follow the specifications requirements, including engineering requirements

Question 134:

Reference: A4206 Detail 2; A1404; Spec 10 80 00 2.1.5
Keynote 10 80 00.F05 calls for a roof access hatch. A1404 shows this opening as Ladder access from Mech Rm below in the attic floor, and spec 10 80 00 2.1.5 only specifies a fire-rated attic access hatch, 559 x 914. Please confirm hatch type and clear opening. The opening governs ladder width, rail spacing and rail extension through the hatch.

Answer 134:

Please provide access hatch as per spec section 10 80 00, 2.1.5. Please provide the ship ladder in accordance with 05 50 00, 2.3.10

Question 135:

Reference: A4206 Details 1 & 2; Spec 05 50 00 2.3.10
Spec 2.3.10 gives the treads (6 mm checker plate) and rails (38 mm Sch 40 at 1200 max.) but not the clear width between stringers, the stringer size, or the handrail extension above the hatch. Please confirm the required width and rail extension, and confirm stringer design is by the fabricator's engineer per SB-8.

Answer 135:

The ship ladder shall be designed and fabricated in accordance with 05 50 00, 2.3.10. Please follow the specifications requirements, including engineering requirements

Question 136:

Can we provide substitution for CLT thickness and grades if they pass under span and loading conditions as per plan?

Answer 136:

Yes

Question 137:

Reference: A4206 Detail 2; A1403
Detail 2 notes 'ladder mechanically fastened to structure' at the top, with no detail. The top lands at the west wall of Mech Rm 305 (wall type 5B6B c, wood stud) and the CLT edge at the hatch. Please confirm the anchorage substrate and fastener type, and confirm that solid blocking at bracket locations is by the framer.

Answer 137:

Please follow the specifications requirements, including engineering requirements

Question 138:

Reference: A1400; A1300; Spec 05 50 00 2.3.9
The ladder from Corr 118 (L1) to Corr B103 (B1) appears only as a symbol on A1400 and an opening on A1300. There is no elevation or detail. Rise from the

datums is 3050 (B1 at -3050 to L1 at 0). Please confirm ladder width, rung spacing, rail section, stand-off from the wall, required rail extension above L1, and what the top of the ladder ties to.

Answer 138:

Please follow the specifications requirements, including engineering requirements

Question 139:

Reference: A1401; A1300
The 1100 x 1164 floor opening in Corr 118 (inside exterior door D118) has no guard, hatch or gate shown, and neither Section 05 50 00 nor 10 80 00 covers one. Please confirm what protection is required at the opening and which section supplies and installs it.

Answer 139:

Protection is not required. This is a means of egress from the basement only.

Question 140:

Reference: A1400; S200
The ladder mounts to the north concrete wall of Corr B103 (CW1 per S200). The anchor type is not indicated. Please confirm.

Answer 141:

Please follow the specifications requirements, including engineering requirements

Question 142:

Reference: A4202 Details 4 & 5; A1403
A4202 shows the Stair B ladder (keynote 05 50 00.F01, labelled 'Roof Access Ladder') in plan and section with no dimensions. Rise from the datums is 3050 (L3 at 6300 to T/O L3 at 9350). Please confirm ladder width, rung spacing, rail section, stand-off from the north wall, location along the wall relative to the area of refuge, and rail extension above the hatch.

Answer 142:

Please follow the specifications requirements, including engineering requirements

Question 143:

Reference: A4202 Detail 5; A1404; Spec 10 80 00 2.1.5; Spec 05 50 00 2.3.9.4
Keynote 10 80 00.F05 calls this a roof access hatch, but it sits in the attic floor at T/O L3 (A1404: 'Ladder access from stair below'). Spec 10 80 00 2.1.5 only covers a fire-rated attic hatch, 559 x 914. Please confirm hatch type, clear opening and curb height (curb not dimensioned). Also confirm whether the anti-climb security door in spec 05 50 00 2.3.9.4 (roof ladders) is required here. This is the same hatch question as RFI 004.

Answer 143:

Please follow the specifications requirements, including engineering requirements

Question 144:

Reference: A4202 Detail 5; A1403
The ladder mounts to the north wall of Stair B, wall type 5B6B c on A1403 (45 min, 38x140 wood stud, ULC U344). Detail 5 shows bracket symbols on the rails with no size, spacing or fastener. Our pricing assumes wall anchorage only (see RFI 014), so the wall brackets carry all ladder load. Please confirm:
- Bracket design and spacing, and fastener type
- Solid blocking at bracket heights is by the framer
- Which face of the wall has the structural sheathing
- Fastening through the rated assembly is acceptable

Answer 144:

Please follow the specifications requirements, including engineering requirements

Question 145:

Reference: A4202 Detail 5; A1404
Our pricing assumes the ladder anchors to the wall only, with no base fixing; please confirm this is acceptable. Detail 5 shows the rails extending above the attic floor and hatch curb (not dimensioned). No wall or framing behind the ladder in the attic is shown, so the top wall bracket would be at or below the attic floor. Please confirm whether the extension can cantilever from the top bracket or must tie to the hatch curb or attic framing (SB-8 design by the fabricator's engineer). As drawn, the rails also run up through the curb opening, which would stop the

hatch lid from closing. Please confirm whether the rails should stop at the hatch frame with a safety post instead.

Answer 145:

Please follow the specifications requirements, including engineering requirements

Question 146:

Access-Control Server Requirements:
Please confirm whether the ICT Protege GX software will be installed on an Owner-supplied or contractor-supplied server/PC. If contractor-supplied, please provide the required specs requirements for the server/PC.

Answer 146:

Contractor supplied PC, refer to ICT for minimum specifications.

Question 147:

Intercom System Substitution:
Please confirm whether an Aiphone intercom solution may be proposed as an approved equivalent to the specified Akuvox system, provided it meets or exceeds all functional, accessibility, integration, programming, commissioning, warranty, and support requirements.

Answer 147:

No substitutions, must be Akuvox (client requirement).

Question 148:

Video-Surveillance Camera Substitution:
Please confirm whether Digital Watchdog cameras may be proposed as an approved equivalent to the specified Axis cameras, provided they meet or exceed all functional, technical, performance, security, integration, warranty, and support requirements and are fully compatible with the Digital Watchdog Spectrum VMS.

Answer 148:

No camera manufacturer substitutions are allowed, cameras must be AXIS (client requirement).

Question 149:

Specification section 10 80 00, page 2 of 5 lists Entrance Mats (EM) but the drawings do not show them. Please confirm if entrance mats are required and show their location on the drawings.

Answer 149:

Entrance Mats are indicated on 1/A4401, in Vest 101 & Vest 108

Question 150:

Addendum No. 2 was issued on October 9, 2026 and contains a significant volume of new and revised information. With the Thanksgiving holiday on October 12, bidders had only four business days to review it before the October 16 deadline for questions. In addition, Addendum No. 3 was issued at noon on

October 15, 2026, leaving less than one business day to review its contents and submit any resulting questions. To allow bidders to properly review both addenda, we respectfully request that the Region extend the deadline for questions by at least five (5) business days, with a corresponding extension to the deadline for issuing addenda.

Answer 150:

Refer to Addendum 4

Question 151:

In light of the volume of information issued in Addendum No. 2 (October 9, 2026) and Addendum No. 3 (October 15, 2026), and the shortened review period over the Thanksgiving week, we respectfully request that the Region extend the Submission Deadline by two (2) weeks. An extension will allow bidders to obtain complete and competitive sub-trade coverage, particularly for the delegated design items, which require engagement of outside engineers. This will result in more accurate pricing for the Region.

Answer 151:

Refer to Addendum 4

Question 152:

Section 01 40 00, 1.4.1 states that the Owner will retain and pay for independent inspection and testing agencies, except as otherwise specified. However, 1.4.3 refers to a cash allowance in Section 01 21 13 for inspection and testing retained and paid by the Contractor, and the only testing allowance in Section 01 21 13 and the Bid Form is for air tightness testing. Please confirm:

Will the Owner retain and pay for concrete testing (Section 03 30 00), soils and

compaction testing (Division 31), and testing of site concrete, including light standard and sign bases?
If any of this testing is the Contractor’s responsibility, will the Region add a cash allowance for inspection and testing, as referenced in Section 01 40 00, 1.4.3?

Answer 152:

Refer to answers #1 & #34 of this addendum

Question 153:

SC 8 – GC 3.4.3, Acceleration at no cost: Please confirm that the Owner’s right to order increased labour, equipment or working hours at no cost applies only where the delay is caused by the Contractor. Where delays are caused by the Owner, the Consultant or other causes under GC 6.5.1 and 6.5.2, we request confirmation that the Contractor is entitled to recover the costs of any required acceleration.

Answer 153:

The Contract Documents govern. Any entitlement to additional time or compensation resulting from delays shall be determined in accordance with the applicable provisions of the Contract. This response does not modify the Region's rights under GC 3.4.3 or acknowledge any entitlement to acceleration costs beyond that expressly provided in the Contract Documents.

Question 154:

What depth is the topsoil for sod outside of soil zones? The drawings suggest 150mm depth, but the specifications suggest 450mm which we believe could be a mistake? Please advise

Answer 154:

That is correct. For sod outside of soil volume areas, 150mm depth topsoil is sufficient. The specification has been revised with addendum 1. For planting beds featuring perennials and shrubs outside of soil zones use the topsoil depth 450mm as defined in the specifications.

Question 155:

Can we get a clearer detail for the wood privacy fence connection to the C.I.P. retaining wall? Detail 3/L.5 doesn't make sense to us and it's very unclear how the fence posts are supposed to be secured to the wall - it looks as if the steel base plate is meant to be embedded into the concrete with about 100mm of it protruding out the back of the wall below grade. Please advise.

Answer 155:

The wall expands to the redline at the posts to allow for the baseplate. This creates 400x400 piers at all posts. No addendum is to be made.

Question 156:

Proposed Substitution for Kramer Equipment :
Section 27 41 00 identifies several Kramer products as the basis of design. Please confirm whether a complete, functionally equivalent Audio-Visual solution using Crestron and other recognized Tier 1 manufacturers may be proposed as an approved equivalent.

Answer 156:

Alternative products will only be considered if the Bidder satisfies the requirements listed in Document 1 of 5, Article 1.7 and no later than 10 days prior to the bid closing date.

Question 157:

Please confirm whether the following products may be submitted as approved equivalents:
• Crestron DM-NAX-AMP-X300 networked audio amplifier
• Crestron DM-NVX-360 AV-over-IP encoder/decoder
• Crestron TSW-1070-W-S touchscreen
• Crestron CP4N control system
• Crestron SAROS PD6T pendant speaker
• NETGEAR M4250-26G4XF-PoE+ managed network switch
• Crestron MC4 compact control system
• Crestron IRP2 infrared emitter probe

Answer 157:

Alternative products will only be considered if the Bidder satisfies the requirements listed in Document 1 of 5, Article 1.7 and no later than 10 days prior to the bid closing date.

Question 158:

Structured Cabling Manufacturer:
Section 27 10 00 identifies Belden as the specified structured cabling manufacturer and requires a certified manufacturer-supported solution. However, other Division 27 sections also reference CommScope and Panduit as acceptable manufacturers for the copper and fibre cabling infrastructure.
Please confirm whether an end-to-end structured cabling solution from CommScope including copper and fibre cabling, connectivity, patch panels, fibre enclosures, patch cords, testing, certification, and the applicable manufacturer warranty, would be accepted as an approved equivalent.

Answer 158:

Alternative products will only be considered if the Bidder satisfies the requirements listed in Document 1 of 5, Article 1.7 and no later than 10 days prior to the bid closing date.

Question 159:

Parking-Lot Camera Connectivity:
Please confirm whether the pole-mounted parking-lot cameras require fibre-optic connectivity or whether extended-reach copper cabling is acceptable.

Answer 159:

Fiber - optic or extended reach copper are both acceptable.

Question 160:

Blu-ray Player Supply:
Section 27 41 00 includes a Blu-ray player as part of the Amenity Room Audio Visual system.
Please confirm whether the Blu-ray player is:
• Supplied by the Owner and installed by the Audio-Visual contractor, or
• Supplied and installed by the Audio-Visual contractor.
If contractor-supplied, please provide the required manufacturer, model or minimum performance requirements.

Answer 160:

Contractor supplied, Sony, Samsung or Toshiba consumer models are acceptable.

Question 161:

Video Surveillance Server and Storage Redundancy:
Reference: Page 1976, Section 1.3.2
The specification states:
“The Video Surveillance System shall be designed on a distributed processing architecture employing remote cameras and operator workstations connected to a redundant central server and storage solution.”
Please clarify if a redundant central server and storage requires a secondary complete server and storage to be available for failover should the primary recording server fail.

Answer 161:

A redundant/secondary server is not required.

Question 162:

Replacement Equipment Within 24 Hours:
The specifications reference the provision of replacement equipment within 24 hours.
Please clarify the intent and extent of this requirement:

a) Does this require the contractor to provide temporary loaner equipment within 24 hours while the original equipment is being repaired?
b) Does the requirement apply only to equipment considered critical to system operation?
c) Is permanent replacement of defective equipment required within 24 hours?
d) Does the 24-hour period include weekends and statutory holidays?
e) Is this requirement applicable during construction, commissioning, the warranty period or all three?

f) Is an onsite spare-equipment inventory required as part of the contract?

Answer 162:

a) Yes
b) Yes
c) Yes
d) No
e) Warranty Period
f) Yes

Question 163:

In-Suite Telecommunications Cabling:
Please confirm whether all telecommunications cabling within the residential suites will be supplied and installed by Bell, Rogers, or another service provider.

Answer 163:

In suite cabling, pathways and P3000/media-panel are the responsibility of the bidder/contractor and to be included for.

Question 164:

Primex P3000 Communications Panels:
Please confirm whether the Primex P3000 residential communications panels, including associated conduits and pathways, will be supplied and installed by others.

Answer 164:

In suite cabling, pathways and P3000/media-panel are the responsibility of the bidder/contractor and to be included for.

Question 165:

Fibre-Optic Enclosures and Connectivity:
Please provide the fibre-optic enclosure and connectivity requirements, including enclosure capacity, fibre type, strand count, connector type, adapter panels, splice trays, and termination method.

Answer 165:

In suite cabling, pathways and P3000/media-panel are the responsibility of the bidder/contractor and to be included for.

Question 166:

Please refer to Q/A#2 from Add#2, Usually, Owner engages the third-party testing & inspection consultant including building science and paid by the Owner. Please confirm that the Owner will higher third-party consultants and pay for all testing & inspections required.

Answer 166:

Refer to answers #1 & #34 of this addendum

Question 167:

Please refer to Add#2, Documents, 4. Appendix C -Appendix C – Cash Allowances, row 2 Signage and Graphics - $70,000 and row 3 Irrigation - $10,000; delete in its entirety. Revise Appendix C - Cash Allowances subtotal to

$50,000. Please advise what items are covered under the cash allowance amount $50,000?

Answer 167:

Air tightness testing

Question 168:

The Proposed Social Housing Development Construction Vibration Zone of Influence Assessment on June 16, 202 recommends beginning of construction vibration levels are monitored at the site & Pre-Conditioned Surveys. It is also noted in the General Conditions- " Seismographs must be installed and operated by a qualified subcontractor specializing in vibration control, analysis, and soil movement" & "Pre-construction condition surveys must be performed by a qualified Subcontractor who is a recognized expert in this field and acceptable to the Contract Administrator"

Answer 168:

We have confirmed that the Town of Whitby requires the completion of Vibration Monitoring Programs and Pre-Construction condition surveys are required in accordance with the recommendations of the "Construction Vibration Zone of Influence Report" completed by EXP (June 2025). Applicant to provide provisions for such items in tender pricing

Question 169:

Construction Management Report prepared by D.G Biddles under Section 12 Vibration Monitoring Program and Condition Assessment- A Vibration Monitoring Program will not be required for the subject property and pre-condition assessment will be completed prior to the commencement of construction work.

Answer 169:

We have confirmed that the Town of Whitby requires the completion of Vibration Monitoring Programs and Pre-Construction condition surveys are required in accordance with the recommendations of the “Construction Vibration Zone of Influence Report” completed by EXP (June 2025). Applicant to provide provisions for such items in tender pricing.

Question 170:

Please advise and provide us with recommended manufacturers to use for self-levelling material like Maxxon Gyp-Crete 2000 MF, Ardex K 520, Mapie Novoplan or Sikafloor level 25

Answer 170:

Section 03 51 13A has been added as part of this addendum.

Question 171:

At Level 2 between gridlines C and E, the specified panel is a 9-ply, 245 mm CLT panel (E1 grade), as shown in the example location in Figure 1. Element5 completed a WoodWorks Sizer check confirming that a 5-ply, 175 mm E1M10 XL panel would be adequate based on a superimposed dead load of 3.2 kPa and a live load of 1.9 kPa. The calculation is attached on the next page (Figure 2), along with the APA document outlining Element5’s CLT strength parameters (Figure 3).

Answer 171:

The thicker CLT was used intentionally to keep a consistent ceiling height in the amenity space below.

Question 172:

Please let us know whether substitutions such as these and at any other locations of similar conditions, can be implemented with the understanding that they are acceptable.

Answer 172:

Alternative products will only be considered if the Bidder satisfies the requirements listed in Document 1 of 5, Article 1.7 and no later than 10 days prior to the bid closing date.

Question 173:

Please provide the fibre-optic enclosure and connectivity requirements, including enclosure capacity, fibre type, strand count, connector type, adapter panels, splice trays, and termination method.

Answer 173:

LC termination, OM4 fibre, 12 strand.

Question 174:

ACCESS CONTROL

1. Door list: door numbers are not final and hardware schedule Set 04 lists no doors. Please confirm the final list of access controlled doors, plus door thickness and handing for the 24 wireless lock suites and 6 barrier-free suites.
2. Barrier-free suites: we are assuming a reader and strike on these 6 doors. Please confirm, and confirm who supplies the strikes and power supplies.

3. Readers: the spec calls for ICT field devices but also mentions HID readers, and the hardware schedule reader part differs from the ICT reader. Is the ICT keypad reader acceptable?
4. Wireless: the drawings show a gateway and RF node per floor. Please confirm the intent, and whether the locks are to be online or offline. ICT wireless locks, online.
5. Life safety: which doors use maglocks, and will the fire alarm contractor supply the release relays? The spec describes a 15 second delayed egress but the code report does not mention it. Does any door require it? No maglocks specified in hardware sets
6. Elevator: please confirm the elevator vendor handles car side card access and we connect and program the interface.

Answer 174:

1. Set#04 is for door D106
2. Hager to supply the electric strikes and the auto operator will power the strikes.
3. ICT keypad/readers with OSDP connections are required, references to HID readers will be removed in addendum.
4. ICT wireless locks, online.
5. No maglocks specified in hardware sets
6. Div 28 is responsible for card readers and programing interface

Question 175:

CAMERAS

1. We count about 27 cameras (11 outside including 2 pole mounts, 16 inside). Please confirm, and confirm who supplies poles, bases and underground conduit. The spec puts video storage in the data centre room but the equipment is shown on the riser in B101 - which is correct, and who supplies it?

2. Addendum 3 (28 21 00, 1.7) puts dedicated CCTV PoE switches in our scope. How many comm rooms or IDFs are there and where? Are the dedicated patch panels ours or Div 27? Can the intercom stations share these switches?

Answer 175:

1. Video storage is to be installed in ELEC & COMMS B101, this to be provided by Division 28.
2. Intercom will connect to client supplied switches

Question 176:

There is groundwater drain piping layout on drawing M-200. Please provide the specifications for this piping.

Answer 176:

Specification section 23 13 00 will be updated to include groundwater drainage piping and issued in an addendum.

End of addendum